



**STATE OF HAWAII**  
**OFFICE OF HAWAIIAN AFFAIRS**  
560 NORTH NIMITZ HIGHWAY, SUITE 200  
HONOLULU, HAWAII 96817

March 31, 2022

TO: Interested Parties

FROM: Michelle Jordan  
Procurement Supervisor

SUBJECT: Request for Quotation No. LLP 2022-027, Addendum No. 1  
Gate Installation & Repair Services at Wahiawā Lands

This Addendum 1 is to notify interested Offerors of the additional specifications to the Scope of Work.

The Scope of Work is hereby amended to state:

- A. The Successful Offeror shall provide gate installation services that will support the OHA in maintaining its Whitmore and Kamananui gates located at Wahiawā Lands, which shall include, but may not be limited to, the following:
- E. The Successful Offeror shall assess two (2) gates on the OHA Wahiawā Lands to determine the extent of the damage.
- F. The Successful Offeror shall provide their written recommendations with cost estimates for replacement to the OHA.
- G. Once the OHA decides on the best option for replacement, the Successful Offeror shall submit a timeline for installation.
- H. The Successful Offeror shall conduct the replacement according to the agreed upon timeline and will coordinate access to the project site with the OHA.

## Gate Specifications:

Details of gate specification will be determined in consultation with the Successful Offeror and the OHA.

However, the following specification are anticipated:

- A newly fabricated gate shall have the same dimensions as the current gate.
- The replacement shall be the same type/style gate, but selected materials may be upgraded to those which can withstand similar damage in the future.
- All products and services shall be in accordance with all applicable federal, state and local statutes, rules, ordinances, etc.

### Whitmore Gate

- Full Gate Replacement
- Please review the layout below for gate specifications.
- Replacement of two drop rods
- OSHA standard reflective tap
- Preventative Measure – Gate Buffer
  - o 3/8” chain in front of gate with two posts 3 ½” posts
  - o Installed three feet deep
  - o 3 to 5 feet in front of gate (exact location to be determined)
  - o S shaped rod to aid in locking the chain to post

### Kamananui Gate

- Full Gate Replacement
- Please review the layout below for gate specifications.
- Installation of two drop rods (currently there are no drop rods)
- OSHA standard reflective tap
- Preventative Measure – Gate Buffer
  - o 3/8” chain in front of gate with two posts 3 ½” posts
  - o Installed three feet deep
  - o 3 to 5 feet in front of gate (exact location to be determined)
  - o S shaped rod to aid in locking the chain to post